

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-03735-00-01

LEASE NAME Buell

WELL NUMBER 2

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

0 Ft. from S Section Line

0 Ft. from E Section Line

SEC. 10 TWP. 9 RGE. 16 (E) or (W)

COUNTY Rooks

LEASE OPERATOR Harold Krueger Co.

ADDRESS Box 247, Natoma, Kansas 67651

PHONE# (913) 885-4701 OPERATORS LICENSE NO. 5769

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 9-23-40

Plugging Commenced 5-16-88

Plugging Completed 5-16-88

The plugging proposal was approved on 5-11-88 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? yes

Producing Formation NA Depth to Top Bottom T.D. SWD 1400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				4½	1700	None
				5½	3400	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforations at 900-950' and 1200-1250'. Tubing at 1340'. Pumped 35 sks cement with ½ flocele down the tubing. Circulated to surface. Pulled tubing out of hole. Hooked up to 5½ casing and pumped 10 sks cement down casing. Circulated out 4½. Shut in 5½. Hooked up to 4½ and pumped 105 sks cement. Shut in w/250 PSI. Well plugged. Job complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No.

Address Hays, Kansas 67601

STATE OF KANSAS COUNTY OF OSBORNE, ss.

Dean E. Wineland

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dean Wineland

(Address) Natoma, Kansas 67651

RECEIVED
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 13th day of June, 1988

6-14-1988
LOIS A. DOTY
Notary Public

My Commission Expires 12-15-88
Wichita, Kansas

