

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20184-00-00

RECEIVED
STATE CORPORATION COMMISSION
FEB 17 1969
CONSERVATION DIVISION
Wichita, Kansas

2-17-69

Operator's Full Name R. G. Smith.

Complete Address: 602 Rule Building, Wichita, Kansas.

Lease Name Hill Well No. 1

Location CSW-SE Sec. 26 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3975'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Gabbert-Jones, Incorporated,

Address: 830 Sutton Place, Wichita, Kansas. License No. _____

Operation Completed: Hour 11:30PM Day 10 Month 2 Year 1968

The Above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 252 Sx.
Top of Dakota Section @ 925'.

Circulated hole with heavy mud. Pulled DP to 1140' and displaced 100 Sx, cement thru
DP from 1140' to 815'. Pulled DP to 275' and displaced 20 Sx, cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx, cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/17/69

INV. NO. 9328-11