

KANSAS

24
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20239-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 12 1969
CONSERVATION DIVISION
Wichita, Kansas

12-12-69

Operator's Full Name Petroleum, Incorporated.

Complete Address 300 West Douglas, Wichita, Kansas.

Lease Name Brown "AB" Well No. AB-1 1

Location App. GS/2-SW-SW Sec. 26 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 4020'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Garvey Drilling Company,

Address Box # 261, Great Bend, Kansas. License No.

Operation Completed: Hour 1:30 PM Day 9 Month 12 Year 1969

The above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 770'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 12/12/69
INV. NO. 1023-W