

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20371-00-00

12-26-73
RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company & P and S Petroleum,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Brown Well No. 1

Location SW-NW-SE Sec. 26 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 3405'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 6:30 PM Day 16 Month 12 Year 1973

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated-with 125 Sx.
Top of Dakota section @ 1025'.

Circulated hole with heavy mud. Pulled DP to 1250' and displaced 110 Cu. Ft. cement
thru DP from 1250' to 925'. Pulled DP to 185' and displaced 30 Cu. Ft. cement thru
DP from 185' to 110'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: H. L. Dickel
Well Plugging Supervisor

DATE 12/28/73

INV. NO. 8340-W