

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-179-30061-00-00

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1965
9-21-65
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name C & G. Drilling Company,

Complete Address: 107 Rule Building, Wichita, Kansas.

Lease Name Brown Well No. 1

Location SW-NE-NW Sec. 26 Twp. 8 Rge. (E) (W) 27

County Sheridan Total Depth 4000

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. _____

Operation Completed: Hour 4:00PM Day 18 Month 9 Year 1965

The Above well was plugged as follows:

279'---8 5/8" Surface pipe, cement circulated with 165 Sx.

Circulated hole with heavy mud, set plug @ 550' and displaced 20 Sx.

cement thru DP. Heavy mud to 270', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP: Heavy mud to 35', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Dech
Well Plugging Supervisor

DATE 9/21/65

INV. NO. 1841-W