

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas
4/21/69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Theodore Gore,

Complete Address 650 Fourth National Bank Building, Wichita, Kansas.

Lease Name Karnes Well No. 1

Location NW NW SE
140' ENL & 140' FWL of SE/4 Sec. 27-087 8 Rge. (E) (W)27

County Sheridan Total Depth 3554'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 2:30PM Day 16 Month 4 Year 1969

The above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1530' and displaced 100 Sx. cement
thru DP from 1530' to 1205'. Pulled DP to 240' and displaced 20 Sx. cement thru DP
from 240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/21/69
INV. NO. 9637-4

Signed: W. L. Nichols
Well Plugging Supervisor