

P

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20070-00-00

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Ben J. Tepper,

Complete Address: 7751 Carondelet, Clayton, Mirrouri.

Lease Name Koster Well No. 1

Location SE-SE-NW Sec. 32 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4235

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Paine Drilling, Incorporated,

Address: Drawer "D", Hill City, Kansas. License No. _____

Operation Completed: Hour 1:30PM Day 12 Month 2 Year 1968

The Above well was plugged as follows:

233'--7" OD Surface pipe, cement circulated with 135 Sx. (6 1/2" Hole).
Dakota section from 1460' to 1600'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 65 Sx. cement thru
DP from 1625' to 1305'. Pulled DP to 245' and displaced 15 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom
of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

FEB 15 1968
CONSERVATION DIVISION
Wichita, Kansas

M. R. Deibel
Well Plugging Supervisor

INVOICED

DATE 2-15-68

NEW NO. 7268-W

2-15-68