

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20075-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 28 1968  
CONSERVATION DIVISION  
Wichita, Kansas

228-68

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Ben J. Tepper,

Complete Address: 462 South Pershing, Wichita, Kansas.

Lease Name Koster Well No. 2

Location NE-NE-NE Sec. 32 Twp. 8 Rge. (E) (W) 29

County Graham Total Depth 4150'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Paine Drilling Company, Incorporated,

Address: Box "D", Hill City, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:30 PM Day 26 Month 2 Year 1968

The Above well was plugged as follows:

233'--7" OD Surface pipe, cement circulated with 135 Sx.  
Dakota section from 1575' to 1375'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 65 Sx. cement thru

DP from 1600' to 1280'. Pulled DP to 240' and displaced 15 Sx. cement thru DP from

240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom

of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dehols  
Well Plugging Supervisor

DATE 3/28/68

INV. NO. 2338-W