

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-179-20165-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
12-9-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Benjamin B. Tepper,

Complete Address: 7751 Carondelet Avenue, Clayton, Missouri.

Lease Name Koster Well No. 4

Location SE-NE-NW Sec. 32 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4141

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Paine Drilling, Incorporated,

Address: Box "D", Hill City, Kansas. License No.     

Operation Completed: Hour 2:45 PM Day 6 Month 12 Year 1968

The Above well was plugged as follows:

221'--7" OD Surface casing, cement circulated with 130 Sx. (6 3/4" hole).  
Top of Dakota section @ 1450'.

Circulated hole with heavy mud. Pulled DP to 1625' and displaced 65 Sx. cement thru  
DP. Pulled DP to 245' and displaced 15 Sx. cement thru DP. Pulled DP, set bridge @  
40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

Signed: *M. L. Dickel*  
Well Plugging Supervisor

INVOICED

DATE 12/9/68

INV. NO. 8968-W