

15-179-20289-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 8 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,
Complete Address Suite 500, Century Plaza, Wichita, Kansas.
Lease Name Currier Well No. 1
Location CSW-NW Sec. 34 Twp. 8 Rge. (E) (W)29
County Sheridan Total Depth 4248'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated _____
Plugging Contractor Above
Address _____ License No. _____
Operation Completed: Hour 3:30 PM Day 2 Month 10 Year 1971

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 100 Sx. cement thru
DP from 1525' to 1200'. Pulled DP to 245' and displaced 25 Sx. thru DP from 240' to
170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10-8-71

INV. NO. 4442-W