

15-179-20378-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1974
CONSERVATION DIVISION
Wichita, Kansas

4/15/74

Operator's Full Name John P. Jenkins,

Complete Address Suite 1000, Century Plaza, Wichita, Kansas.

Lease Name Carrier Well No. 1

Location NW-NW-NW Sec. 34 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 3585'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor John O. Farmer, Incorporated,

Address 370 W. Wichita, Russell, Kansas. License No.

Operation Completed: Hour 12:30 PM Day 11 Month 4 Year 1974

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement
thru DP from 1500' to 1175'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 4/15/74
INV. NO. 8929-W

Signed: M. L. Daniels
Well Plugging Supervisor