

15-179-20094-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

**STATE CORPORATION COMMISSION**

**CONSERVATION DIVISION AGENT'S REPORT**

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
4/19/68  
APR 19 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Rock Island Oil & Refining Company, Incorporated,

Complete Address: 321 West Douglas, Wichita, Kansas.

Lease Name Pratt Well No. B-1

Location SW-SE-SE Sec. 35 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4170'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Kans. License No.     

Operation Completed: Hour 7:00 PM Day 14 Month 4 Year 1968

The Above well was plugged as follows:

220'--8 5/8" Surface pipe, cement circulated with 190 Sx.  
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru  
DP from 1400' to 1080'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: M. D. Nichols  
Well Plugging Supervisor

DATE 4/19/68  
INV. NO. 4611-W