

15-179-20196-0020

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

APR 8 1969

CONSERVATION DIVISION
Wichita, Kansas

4/8/69

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Koch Exploration Company,

Complete Address: P. O. Box #2256, Wichita, Kansas.

Lease Name Pratt Well No. 4

Location 150' NW of CNW-SW Sec. 35 Twp. 8 Rge. (E) (W) 29

County Sheridan Total Depth 4195'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Ks. License No. _____

Operation Completed: Hour 6:00PM Day 5 Month 4 Year 1969

The Above well was plugged as follows:

223'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1270'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 100 Sx. cement thru
DP from 1500' to 1175'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. Deibel
Well Plugging Supervisor

DATE _____

INV. NO. _____