

15-179-20308-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1972

CONSERVATION DIVISION
Wichita, Kansas

7/18/72

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Petroleum Reserve Corporation
Complete Address 225 Cravens Building Oklahoma City, Oklahoma
Lease Name Hughes Well No. 1
Location C SW NE Sec. 35 Twp. 8 Rge. (E) (W) 29
County Sheridan Total Depth 4180'
Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A XX
Other well as hereafter indicated _____
Plugging Contractor Sage Drlg.
Address Wichita, Kansas License No. _____
Operation Completed: Hour 12 M Day 13 Month 7 Year 1972

The above well was plugged as follows:

RTD 4180' 8 5/8 csg set at 246' cwc 175 sk. Cmt. Mat. 50-50 poz cmt W/4% added gel.
Gunned pits, circulated heavy mud, set cementing plug at 1450' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED

DATE 7/18/72
INV. NO. 0045-W