

15-193-20040-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1973

CONSERVATION DIVISION
Wichita, Kansas

11/17/73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Boeger Well No. A-1

Location CSW-NE Sec. 28 Twp. 8 Rge. (E) (W) 32

County Thomas Total Depth 4690'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Incorporated,

Address Box #698, Great Bend, Kansas. License No. 670

Operation Completed: Hour 3:45 PM Day 16 Month 11 Year 1973

The above well was plugged as follows:

451'--8 5/8" Surface casing, cement circulated with 325 Sx.
4689'--4 1/2" Production casing cemented on bottom with 125 Sx. No plug back indicated.
Top perforations from 4569' to 4574'.

Pushed plug to 4550', sand back to 4525' and set 4 Sx. cement with dump bailer.

Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from 1875' to 1550' then 27 sacks gel from 1550' to 470' and followed with 30 Cu. Ft. cement from 470' to 395' then 9 sacks gel from 395' to 35' and finally 10 Cu. Ft. cement from 35' to bottom of cellar. Maximum pump-in pressure-100#. FSIP-50#. (Mudding and cementing operations by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

DATE 11/20/73

INV. NO. 8189-W

Signed: R. S. Nichols
Well Plugging Supervisor