

KANSAS

*A* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20007-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 12 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
11-12-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name Saddler Well No. 1

Location CSW-NW Sec. 32 Twp. 8 Rge. (E) (W) 32

County Thomas Total Depth 4402

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Rains & Williamson Oil Company, Incorporated,

Address: 1425 Wichita Plaza Building, Wichita, Ks. License No.

Operation Completed: Hour 7:45 PM Day 8 Month 11 Year 1968

The Above well was plugged as follows:

276'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 2025'.

Circulated hole with heavy mud. Pulled DP to 2250' and displaced 100 Sx. cement thru  
DP from 2250' to 1925'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from  
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Pfeibel*  
Well Plugging Supervisor

INVOICED

DATE 11/12/68  
INV. NO. 8805-W