

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-193-20006-00-00

RECEIVED  
STATE CORPORATION COMMISSION

DEC 13 1974

CONSERVATION DIVISION  
Wichita, Kansas

12-13-74

Operator's Full Name Pickrell Drilling Company

Complete Address 705 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name Basting Well No. 1

Location C NW NE Sec. 34 Twp. 8 Rge. (E) (W) 32

County Thomas Total Depth 4678'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 5 P Day 11 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 4673' 8 5/8 csg set at 364' cwc 200 sk.

5 1/2 csg set at 4420' cw 150 sk cem.

5 1/2 csg PBSD 4320' with PFS (4286-4092)

Set 5 1/2 wood plug at 4000' -poured 20' sd -dumped 4 sk cem W/dump bailer. (4000-3950)

Cutoff & recovered 1922' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk cem. -15 sk gel & water, released 8 5/8 plug & pumped 50 sk cem. by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Massey  
Well Plugging Supervisor

DATE 12/18/74  
INV. NO. 492-W