

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20018-00-00

RECEIVED  
STATE CORPORATION COMMISSION

JUN 16 1969

CONSERVATION DIVISION  
Wichita, Kansas

6-16-69

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Rains & Williamson Oil Co. Inc., and McClure Oil Co.,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name James Sowers Well No. 1

Location CNE-SE Sec. 34 Twp. 8 Rge. (E) (W) 32

County Thomas Total Depth 4370'

Abandoned Oil Well          Gas Well          Input Well          SWD Well          D & A X

Other well as hereafter indicated:         

Plugging Contractor: Rains & Williamson Oil Company, Incorporated.

Address: 1425 Wichita Plaza Building, Wichita, Kans. License No.         

Operation Completed: Hour 7:15 PM Day 11 Month 6 Year 1969

The Above well was plugged as follows:

356'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1625'. Landowner, James Sowers, requests surface casing be  
left open to be used as a fresh water well. (Authorization attached).

Circulated hole with heavy mud. Pulled DP to 1850' and displaced 100 Sx. cement thru  
DP from 1850' to 1525'. Pulled DP to 395' and displaced 25 Sx. cement thru DP. Pulled  
DP to 305' and circulated clear water to surface to clear surface casing of drilling mud.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols

Well Plugging Supervisor

DATE 6/16/69.

INV. NO. 9940-W