

KANSAS

28
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1970

CONSERVATION DIVISION
Wichita, Kansas

12-15-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20034-00-00

Operator's Full Name Braden & Deem, Incorporated,

Complete Address 200 East First, Wichita, Kansas.

Lease Name Jensen Well No. 1

Location NW-NW Sec. 35 Twp. 8 Rge. (E) (W) 32

County Thomas Total Depth 4400'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kans. License No.

Operation Completed: Hour 7:30 PM Day 8 Month 12 Year 1970

The above well was plugged as follows:

360'--8 5/8" Surface casing, cement circulated. (235 Sx.).
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 100 Sx. cement thru
DP from 1775' to 1450'. Pulled DP to 375' and displaced 25 Sx. cement thru DP from
375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. S. Dehals*
Well Plugging Supervisor

INVOICED

DATE 12/15/70
INV. NO. 3063-W