

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20024-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Vacin Well No. B-1

Location CNE-NW Sec. 24 Twp. 8 Rge. (E) (W) 33

County Thomas Total Depth 4770'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 1:15 AM Day 23 Month 9 Year 1969

The above well was plugged as follows:

334'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 100 Sx. cement thru
DP from 1775' to 1450'. Pulled DP to 345' and displaced 20 Sx. cement thru DP from
345' to 285'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

INVOICED

CONSERVATION DIVISION
Wichita, Kansas

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 9/26/69
INV. NO. 541-W

9-26-69