

KANSAS

*Y* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20040-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

128-72  
RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1972  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name National Oil Company, Incorporated,  
Complete Address 200 West Douglas, Suite #500, Wichita, Kansas.  
Lease Name Leak Well No. \_\_\_\_\_  
Location NW-NW-SE Sec. 36 Twp. 8 Rge. (E) (W) 33  
County Thomas Total Depth 4780'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Red Tiger Drilling Company,  
Address 1720 Wichita Plaza Building, Wichita, Kans. License No. \_\_\_\_\_  
Operation Completed: Hour 2:30 AM Day 25 Month 1 Year 1972

The above well was plugged as follows:

340'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1525'.

Circulated hole with heavy mud. Pulled DP to 1750' and displaced 110 Cu. Ft. cement  
thru DP from 1750' to 1425'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru  
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. S. D. Dehals  
Well Plugging Supervisor

DATE 1-28-72

INV. NO. 5094-W