



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Ben J. Tepper,

Complete Address: 7751 Carondelet, Clayton, Missouri.

Lease Name: Koster Well No. 1

Location: SE-SE¹/₄ NW Sec. 32 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4235' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

233'--7" OD Surface pipe, cement circulated with 135 Sx. (6 1/4" Hole). Dakota section from 1460' to 1600'.

Circulate hole with heavy mud. Pull DP to 1625' and displace 65 Sx. cement thru DP. Pull DP to 245' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom of cellar.

RECEIVED
 STATE CORPORATION COMMISSION

2-15-68

FEB 15 1968

CONSERVATION DIVISION
 Wichita, Kansas

W. L. Nichols

Conservation Division Agent