



15-179-20075-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1968
CONSERVATION DIVISION
Wichita, Kansas
228-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drllg. Co. Inc., has this

date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Ben J. Tepper,

Complete Address: 462 South Pershing, Wichita, Kansas.

Lease Name: Koster Well No. 2

Location: NE-NE-NE Sec. 32 Twp. 8 Rge. (E)(W) 29

County: Graham Total Depth 4150' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Born was instructed to plug the well as follows:

233'--7" OD Surface pipe cement circulated with 135 Sx. (6 1/4" Hole).
Dakota section from 1375' to 1575'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 65 Sx.
cement thru DP. Pull DP to 240' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Dehler
Conservation Division Agent