

State of Kansas



15-179-20165-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

### State Corporation Commission

#### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 9 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 12-9-68

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Buane Born of Paine Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Benjamin B. Tepper,

Complete Address: 775/ Carondelet Avenue, Clayton, Missouri.

Lease Name: Koster Well No. 4

Location: SE-NE-NW Sec. 32 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4141 Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Born was instructed to plug the well as follows:

22 1/2" -- 7" OD Surface casing, cement circulated with 130 Sx.  
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1625' and displace 65 Sx. cement thru DP. Pull DP to 245' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
 Conservation Division Agent