

State of Kansas



15-179-20169-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GIAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 24 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 12-24-68

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Duane Born of Paine Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Born guarantees payment of the plugging fee.

Operator's full Name: Benjamin B. Tepper,

Complete Address: 7751 Carondelet, Clayton, Missouri.

Lease Name: Koster Well No. 5

Location: NW-SE-NE Sec. 32 Twp. 8 Rge. (E)(W)29

County: Sheridan Total Depth 4190 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Born was instructed to plug the well as follows:

239'--7" Od Surface casing, cement circulated with 135 Sx. (6 1/2" Hole).  
 Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1625' and displace 65 Sx.  
 cement thru DP. Pull DP to 245' and displace 15 Sx. cement thru DP.  
 Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
 of cellar.

Very truly yours,

Conservation Division Agent