



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 AUG 27 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

8/27/68

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Currier Well No. A-1

Location: SE-NE-NW Sec. 34 Twp. 8 Rge. (E)(W) 29

County: Sheridan Total Depth 4140 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1265'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent