



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 19 1973  
CONSERVATION DIVISION  
Wichita, Kansas

11/19/73

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Rockhold Engineering, Inc., has this

date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Boeger Well No. A-1

Location: CSW-NE Sec. 28 Twp. 8 Rge. (E)(W) 32

County: Thomas Total Depth 4690' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

451'--8 5/8" Surface casing, cement circulated with 325 Sx.  
4689'--4 1/2" Production casing cemented on bottom with 125 Sx. No plug-  
back indicated. Top perforations from 4569' to 4574'.

Push plug to 4550', sand back to 4525' and set 4 Sx. cement with dump  
bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 45 sacks  
gel and 150 Cu. Ft. cement staged.

Very truly yours,

M. L. Dickole  
Conservation Division Agent