

State of Kansas



13-193-20007-00-00

ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

NOV 12 1968

CONSERVATION DIVISION  
Wichita, Kansas

11-12-68

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. Inc has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Saddler Well No. 1

Location: CSW-NW Sec. 32 Twp. 8 Rge. (E)(W) 32

County: Thomas Total-Depth 4402' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Walker was instructed to plug the well as follows:

276'--8 5/8" Surface casing, cement circulated with 275 Sx.  
Top of Dakota section @ 2025'.

Circulate hole with heavy mud. Pull DP to 2250' and displace 100 Sx.  
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent