



15-193-20018-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 16 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 6-16-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Paul Stevens of Rains & Williamson Oil Co., Inc., Imas, this date requested permission to plug the following described well:

Mr. Stevens guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Co., Inc., & McClure Oil Co.,

Complete Address: 1125 Wichita Plaza Building, Wichita, Kansas.

Lease Name: James Sowers Well No. 1

Location: CNE-SE Sec. 34 Twp. 8 Rge. (E)(W) 32

County: Thomas Total Depth 4370' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stevens was instructed to plug the well as follows:

356'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1625'. Landowner requests surface casing be left open to be used as a fresh water well.

Circulate hole with heavy mud. Pull DP to 1850' and displace 100 Sx. cement thru DP. Pull DP to 395' and displace 25 Sx. cement thru DP. Pull DP, to 305' and circulate clear water to surface to clear surface casing of drilling mud.

Very truly yours,

Conservation Division Agent