



15-193-20034-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

DEC 15 1970

CONSERVATION DIVISION  
Wichita, Kansas

12-15-70

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Braden & Deem, Incorporated,

Complete Address: 200 East First, Wichita, Kansas.

Lease Name: Jensen Well No. 1

Location: NW-NW Sec. 35 Twp. 8 Rge. (E)(W) 32

County: Thomas Total Depth 4400' Oil Well

Gas Well  Input Well  SWD Well  D-&A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

360'--8 5/8" Surface casing, cement circulated with 235 Sx.  
Top of Dakota section @ 1550'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 100 Sx.  
cement thru DP. Pull DP to 375' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hullsand 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent