



15-193-20024-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Vacin Well No. B-1

Location: CNE-NW Sec. 24 Twp. 8 Rge. (E)(W) 33

County: Thomas - Total-Depth- 4770' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

334'--8 5/8" Surface casing, cement circulated with 300 Sx.
Top of Dakota section @ 1550'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 100 Sx.
cement thru DP. Pull DP to 345' and displace 20 Sx. cement thru DP.
Pull DP, set Bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

RECEIVED

STATE CORPORATION COMMISSION

SEP 26 1969

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent

926-69