



15-193-20040-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 28 1972
CONSERVATION DIVISION
Wichita, Kansas

1-28-72
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: National Oil Company, Incorporated,

Complete Address: 200 West Douglas, Suite 500, Wichita, Kansas.

Lease Name: Leak Well No. 1

Location: NW-NW-SE Sec. 36 Twp. 8 Rge. (E)(W) 33

County: Thomas Total Depth 4780' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

340'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota @ 1525'.

Circulate hole with heavy mud. Pull DP to 1750' and displace 110 Cu. Ft. cement thru DP. Pull DP to 375' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent