



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 14 1974

CONSERVATION DIVISION
Wichita, Kansas

1-14-74

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Company, Inc. has this
date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc., & Bill J. Porter,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Schielke Well No. 1

Location: CNW-SW Sec. 16 Twp. 8 Rge. (E)(W) 34

County: Thomas Total Depth 4817' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

350'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1700'.

Circulate hole with heavy mud. Pull DP to 1925' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 370' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

H. L. Nichols

Conservation Division Agent