



15-181-19004-00-00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
11-16-70

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Niernberger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Niernberger guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Bergsma Well No. 1-A

Location: App: SW-SW-SW Sec. 11 Twp. 8 Rge. (E)(W) 38

County: Sherman Total Depth 691 Oil Well     

Gas Well      Input Well      SWD-Well      D & A      Lost Hole X

Mr. Niernberger was instructed to plug the well as follows:

375'--7" OD Surface casing, cement circulated with 175 Sx. Surface set 100' in shale. Hole drilled below surface with air. Stuck DP on bottom leaving 6 drill collars and 1 joint DP in hole. Top of fish @ 446'.

Run DP to top of fish and blow hole dry with air. Run 25 Sx. cement from 425' to 300'. Fill hole with mud to 40', set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. G. Nichols  
Conservation Division Agent