



15-181-19005-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1970
CONSERVATION DIVISION
Wichita, Kansas

11-17-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company, has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas,

Lease Name: Bergsma Well No. 1-"B"

Location: App: SW-SW-SW Sec. 11 Twp. 8 Rge. (E)(W) 38

County: Sherman Total Depth: 937' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Ulrich was instructed to plug the well as follows:

608'--8 5/8" Surface casing, cement circulated with 250 Sx. (6 1/4" Hole).
Drilled hole with air below surface casing. Stuck DP and abandoned hole.

Run DP to 600', blow hole dry with air and set 25 Sx. cement from 600'.

Pull DP, fill hole to 40' with mud, set bridge @ 40' with 1/2 sack hulls
and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Diehl
Conservation Division Agent