



15-181-20006-00-00

ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 17 1969
CONSERVATION DIVISION
Wichita, Kansas

3-17-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. A. B. Holaday of Mack Oil Company, has this

date requested permission to plug the following described well:

Mr. Holaday guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Armstrong Well No. 1

Location: CSE-NW Sec. 6 Twp. 8 Rge. (E)(W) 39

County: Sherman Total Depth 5301' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Holaday was instructed to plug the well as follows:

365'--8 5/8" Surface casing, cement circulated with 350 Sx.
Top of Dakota section @ 2150'.

Circulate hole with heavy mud. Pull DP to 2275' and displace 130 Sx.
cement thru DP. Pull DP to 380' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent