

15-173-00655-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick County. Sec. 20 Twp. 26 Rge 2E (E) (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines NW NW SE

Lease Owner Allison & McLaughlin

Lease Name Erdwein Well No. 1

Office Address 715 Brown Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed 4-15-1951

Application for plugging filed " 19

Application for plugging approved " 19


Plugging commenced " 19

Plugging completed " 19

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well J. P. Roberts

Producing formation Depth to top Bottom Total Depth of Well 2999 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	85'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Set bottom plug at 100 feet. Mixed and poured 15 sacks cement through drill pipe. Set top plug at 20 feet. Mixed and poured 10 sacks cement on top.

4-17-51
APR 17 1951
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to A. D. Allison & Co., Inc.,
Address 715 Brown Building, Wichita 2, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
A. D. Allison (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. D. Allison
715 Brown Building, Wichita, Kansas
(Address)

Subscribed and Sworn to before me this 16th day of April, 1951.
My commission expires 7-22-53

Notary Public

23-5091-8 8-50-16M

PLUGGING
FILE SEC 20 T 26 R 2E
BOOK PAGE 20 LINE 6

ALLISON & McLAUGHLIN
#1 ERDWEIN

Sec. 20, Twp. 26S., Rge. 2E.

Sedgwick County, Kansas.

Total Depth 2999'
Comm. 4-2-51
Comp. 4-15-51
CONTR: A. D. ALLISON & CO., INC.

NW NW SE

Elevation: 1398 D. F.

Production: D & A

CASING RECORD:

8-5/8 85'

FORMATION

DEPTH

Soil, shale and shells	40
Shale and lime	85
Lime and shale	150
Lime	370
Lime and shale	900
Shale	1030
Shale and shells	1605
Shale, lime and shells	1725
Shale and lime	1790
Lime and shale	2505
Lime	2715
Shale	2770
Shale and lime shells	2850
Shale and lime	2870
Shale	2953
Lime	2999 - T. D.

TOPS:

Kansas City	2505
Mississippi	2953

Certified true copy of drillers log.

By A. D. Allison

