

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick

County. Sec. 20 Twp. 26 Rge. 2 (E) E (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines C N/2 NW SW

Lease Owner The Black Supply Company, Inc.

Lease Name Sample C ANB KC Well No. 2

Office Address 517 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 12 19 51

Application for plugging filed June 14 19 51

Application for plugging approved June 12 19 51


Plugging commenced June 12 19 51

Plugging completed June 12 19 51

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well D. C. Lilley

Producing formation Depth to top Bottom Total Depth of Well 2998 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with rotary mud from total depth to 110 feet -
wooden plug set @ 110 feet - 15 sax of cement on top of plug.
Hole filled with rotary mud from 110' to 10 feet below top of
cellar - plug at 10 foot and filled to top of cellar with 5
sax of cement.

RECEIVED
STATE CORPORATION COMMISSION
6-16-51
JUN 16 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Black Supply Company, Inc.
Address 517 Union National Bank Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

C. A. Black (owner of well or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. A. Black

C. A. Black - President
The Black Supply Company, Inc.
(Address)

Subscribed and sworn to before me this 15th day of June, 1951

March 18, 1954
My commission expires

Grace S. Hebbert
Notary Public.



PLUGGING
FILE SEC 20 T 26 R 2 E
BOOK PAGE 27 LINE 32

CAPITT DRILLING, INC.

ROTARY DRILLING LOG

Black Supply Co, Inc. & et. al.
 Sample #20
 N/2 - SW/4 Section 20-26-24
 Sedgwick County, Kansas

Date Commenced 6-1-51
 Date Completed 6-12-51

0-35 Shale & Shells
 50 Shale & Shells
 70 Shale & Lime
 95 Lime & Shale
 95' 8 5/8 OD Surface Pipe
 95-195 Lime
 290 Lime & Shale Broken
 300 Red Bed
 390 Lime & Shale Broken
 495 Lime & Shale Broken
 500 Red Rock
 590 Lime & Shale
 650 Lime & Shale
 725 Shale & Shells
 910 Shale & Shells
 940 Lime & Shale
 1035 Shale & Shells
 1045 Red Rock
 1195 Shale & Lime
 1585 Shale & Lime Shells
 1775 Lime & Shale
 1870 Shale & Shells
 2080 Shale & Lime
 2190 Shale & Shells
 2255 Lime & Shale
 2300 Lime
 2360 Lime & Shale
 2498 Shale & Shells
 2535 Lime (Kansas City)
 2625 Lime
 2663 Lime
 2732 Shale & Shells
 2795 Shale & Shells
 2845 Shale & Lime
 2935 Shale & Lime Shells

2935-2950 Shale & Lime
 2937 Shale (Vari-colored)
 2968 Sand
 2971 Sand - Shale
 2998 Lime & Chert (miss.)
 2998 T.D. D & A

Note:
 Hole plugged as follows: / Per
 Dwight Lilly:

Hole filled w/ Rotary Mud
 from T. D. to 110 feet - Wooden
 Plug set @ 110 feet - 15 sax of
 cement on top of Plug. Hole
 filled w/ Rotary Mud from 110'
 to 10 feet below top of cellar -
 Plug at 10 feet and filled to
 top of cellar w/ 5 sax of cement.

L. J. Clappitt

Elevation - 1389 DF
 1386 Gr.

Surface Casing -
~~95'~~ - 8 5/8"
 95'

Formation Tops

Lansing 2497' - 1107
 Base Kansas City
 2663' - 1273
 Burgess Sand 2967' - 1577
 Miss. Lime 2972' - 1582

RECEIVED
 STATE CORPORATION COMMISSION

JUN 16 1951

CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 FILE SEC 20T 26 R 26
 BOOK PAGE 87 LINE 37