


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Sedgwick County. Sec. 19 Twp. 26S Rge. 2 (E) (W)
Location as "NE/CNW/SW" or footage from lines SE/ Corner



Locate well correctly on above
Section Plat

Lease Owner John P. Gaty
Lease Name Tjaden Well No. 2
Office Address 11 Cypress Dr.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Jan. 8 19 50
Application for plugging filed June 29 19 53
Application for plugging approved June 30 19 53
Plugging commenced July 4 19 53
Plugging completed July 4 19 53
Reason for abandonment of well or producing formation Water

If a producing well is abandoned, date of last production June 13, 19 53
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Burgess Depth to top _____ Bottom _____ Total Depth of Well 2948 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back from 2948' to 2930' with sand and six sacks Cement
Mudded to bottom of surface pipe - 2930' to 110'
Set 15' rock bridge with 15 sacks cement at 110'
Mudded to 20'
Set 10' rock bridge with 5 sacks cement at 20'

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1953
7-18-53
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor John P. Gaty
Address 11 Cypress Dr., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Earl Wentworth (employee of owner) ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Earl Wentworth
Mulvane, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July, 19 53

My commission expires December 12, 1955

J. Arnold Dowd
Notary Public.

PLUGGING
FILE SEC 1926R26
BOOK PAGE 111 LINE 16

WELL LOG - Tjaden #2

OPERATOR: Mr. J. P. Gaty
c/o Beech Aircraft Corp.
Wichita, Kansas

LOCATION: SE/C of Section 19,
Township 26 South, Range 2
East, Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Co., Inc.
P. O. Drawer 712
El Dorado, Kansas

PRODUCTION: _____

Farm: Tjaden Well No. 2

Date Commenced: December 20, 1949
Date Completed: December 27, 1949

Total Depth: 2937 feet

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Formation</u>
83	110	Cement	2500	2630	Lime
110	263	Lime	2630	2793	Lime & Shale
263	300	Lime & Shale	2793	2845	Lime & Shale Strks.
300	305	Red Rock	2845	2937	Shale & Lime
305	345	Lime & Shale	2937		Total Depth.
345	375	Shale & Shells			
375	380	Red Rock			
380	410	Lime & Shale Brks.			
410	450	Lime			
450	595	Lime & Shale			
595	600	Red rock			
600	615	Lime & Shale			
615	620	Red Rock			
620	626	Lime & Shale Brks.			
626	640	Lime & Shale			
640	650	Red Bed			
650	925	Lime & Shale			
925	1030	Shale			
1030	1035	Red Bed			
1035	1060	Shale			
1060	1065	Red Bed			
1065	1075	Shale			
1075	1095	Lime			
1095	1220	Shale			
1220	1235	Lime			
1235	1275	Shale & Lime			
1275	1320	Lime			
1320	1450	Shale & Lime Brks.			
1450	1465	Sandy Shale			
1465	1815	Lime & Shale			
1815	1930	Lime & Shale Brks.			
1930	2100	Shale & Lime			
2100	2120	Shale			
2120	2215	Lime & Shale			
2215	2248	Shale & Shells			
2248	2305	Lime			
2305	2325	Shale & Shells			
2325	2450	Limeshells & shale			
2450	2490	Shale & Lime (Rough)			
2490	2500	Shale			

Cable tool Log

*2937-38 Shale + Lime Pebbles
2938-40 Cemented Sand
2940-46 Sand + Shale streaks
2946-48 Pay Sand*

*Show at 2940
increasing with
each run.*

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1950

CONSERVATION

PLUGGING
FILE SEC 19 T 26 R 28
BOOK PAGE 111 LINE 16


Well Log - Tjaden #2 (Cont.)

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Tjaden #2 Well drilled for Mr. J. P. Gaty and completed December 27, 1949.



C. W. Wilson
Secretary-Treasurer

STATE OF KANSAS)
COUNTY OF BUTLER) ss.



SUBSCRIBED AND SWORN TO, Before the undersigned, a Notary Public, in and for the County and State aforesaid this 30th day of December, 1949.



Notary Public

My Commission Expires January 10, 1951.

PLUGGING
FILE SEC-19 T-26 R-22
BOOK PAGE 111 LINE 16

RECORDED
DEC 1 1949
CONSERVATION