

STATE OF KANSAS  
STATE COMMISSION  
2000 Pendergast Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-173-20658-00-00

LEASE NAME JEFFRIES

WELL NUMBER 3 - A MJB KCC

SPOT LOCATION SE/NE/NW

SEC. 22 TWP. 26 RGE. 2 (E) or XXXX

COUNTY SEDGWICK

Date Well Completed \_\_\_\_\_

Plugging Commenced 12/21/88

Plugging Completed 1/4/89

RECEIVED  
STATE COMMISSION  
JAN 6 1989

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR H 30 INC.

ADDRESS 251 Nth Water Suite 10 Wichita, Ks. 67202

PHONE # ( ) \_\_\_\_\_ OPERATORS LICENSE NO. 5107

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Wichita, Ks.

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom PBD 3351'

Show depth and thickness of all water, oil and gas formations.

T.D. 3365  
AMB  
KCC

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				4 1/2"	3351'	1233'
				8 5/8"	205'	101'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. R.S.S. Strung up 4" tools. Run tools into 3300'. Tools stopped @ 1630'. 3 1/2" bailer stopped @ 1630'. Strung up 3" sand pump. Sand Pump stopped @ 1630'. Run 56 jts 2/38" tubing on Ottis Production Packer. Working tubing & packer to 1775'. Csg bad from 1600'. Halliburton pumped down tubing. Circulated hole to surface Run 2 jts 2 3/8" tubing. Working packer & tubing from 1775' to 1835'. Pulled tubing & packer  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor W W DRILLING CO. License No. 6012  
Address RR# 3 Box 66 El Dorado, Kansas 67042

STATE OF Kansas COUNTY OF Butler, ss.

DALE WILSON (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson  
RR # 3 Box 66  
(Address) El Dorado, Ks. 67042



SUBSCRIBED AND SWORN TO before me this 5 day of January 1989

Rebecca K. Farner  
Notary Public

My Commission expires: 9-13-92

Run 81 jts 2 3/8" tubing to 2600'. Halliburton spotted 30 sacks cement @ 2600'. Pulled 33 jts tubing. Halliburton spotted 30 sacks cement @ 1545'. Pulled tubing. Put on long stroke jars & ripper. Picked up on 4 1/2" csg. Csg into. Pulled 24 jts 4 1/2" csg. Pulled 7 jts 4 1/2" csg. Total 31 jts 4 1/2" csg. 1233'. Put rock bridge 300' to 280'. Bail hole dry @ 280'. Had 5 1/2 yds slurry mix cement put from 280' to surface. Rigged down @ 2:00 PM

REBECCA K. FARMER  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPL. EXPIRES