


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Sedgwick County, Sec. 22 Twp. 26 Rge. 2E (X) (X)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NW NE  
Lease Owner Shawver-Graham, Inc.  
Lease Name Lygrisse "C" Well No. 1  
Office Address 204 No. Market, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry  
Date well completed June 14 1949  
Application for plugging filed October 26, 1949  
Application for plugging approved October 27, 1949  
Plugging commenced Oct. 27 1949  
Plugging completed Oct. 31 1949  
Reason for abandonment of well or producing formation dry

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lilley  
Producing formation Depth to top Bottom Total Depth of Well 3208 Feet  
Show depth and thickness of all water, oil and gas formations. 3257 ANB ca

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	3208'	2751'
				8 5/8"	105'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rocked hole from 3257' to 3201'; dumped 5 sacks cement.  
Mudded to 125'; set 10' rock bridge & dumped 10 sacks  
cement; mudded to 10', dumped 3 sacks cement.

RECEIVED  
11-9-49  
NOV 9 1949  
STATE CORPORATION  
COMMISSION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Shawver-Graham, Inc.  
Address 204 No. Market, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

William L. Graham, (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

204 N. Market, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of November 1949

My commission expires 9-3-51 [Signature] Notary Public.

PLUGGING  
FILE SEC 22 T 26 R 2E  
BOOK PAGE 181 LINE 22

LYGRISSE WELL NO. "1-C"

Location: NE NE NE 22-26-2E  
Sedgwick, County, Kansas

Operator: Shawver-Graham, Inc.  
204 N. Market  
Wichita, Kansas

Casing Record: 105' - 8 5/8" Surface Casing  
Cemented with 60 sacks-Red Wing  
3208' - 5 1/2" Casing  
Cemented with 70 sacks

*Min Top 2925  
Viola Top 3204*

LOG

(Figures indicate bottom of formation)

Clay	56	Line-Shale	2150
Line-Shale	305	Shale-Lime	2265
Shale-Red Rock	315	Line	2393
Line-Shale	430	Shale	2495
Red Rock	485	Line-L.C.	2553
Line-Shale	660	Line-Shale	2695
Shale-Lime	975	Shale-Lime	2816
Red Rock	982	Shale-Shells	2886
Shale-Shells	1040	Shale	2895
Shale-Shells	1435	Chat	3038
Shale-Lime	1712	Line-Hard	3160
Line-Shale	1970	Shale	3204
Shale-Lime	2055	Viola-Lime	3208
		T.D.	3208

The undersigned, Shawver-Graham, Inc., hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

SHAWVER-GRAHAM, INC.

By: *J. Shawver*  
President

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK )

BE IT REMEMBERED that on this 10th day of May 1949, before me the undersigned, a notary public duly commissioned in and for the county and state aforesaid, came DWIGHT H. SHAWVER, President, of Shawver-Graham, Inc., a Kansas Corporation, personally known to me to be such officer, and to be the same person who executed as such officer the foregoing instrument of writing in behalf of said corporation, and he duly acknowledged the execution of same for himself and for said corporation.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

*James K. Sturgess*  
Notary Public

My Commission Expires:  
1-29-53

*Cap hole to 3257'  
run 64' liner cemented  
with 15 sacks cement*

FILED  
MAY 22 1949  
26 2E  
27

