

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER 15-173-20,842 00-00

LEASE NAME M & L Land Company

WELL NUMBER 1

1980 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 22 TWP. 26S RGE. 2 (E) or XXX

COUNTY Sedgwick

Date Well Completed 1/26/90

Plugging Commenced 1/26/90

Plugging Completed 1/26/90

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

IFB 8 1990  
 2-8-90  
 CONSERVATION DIVISION  
 Wichita, Kansas

LEASE OPERATOR Vess Oil Corporation

ADDRESS 8100 E. 22nd St. N Building 300 Wichita, Ks. 67226

PHONE# (316) 682-1537 OPERATORS LICENSE NO. 5030

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1/25/90 (date)

by Ralph Tittel (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation / Depth to Top / Bottom T.D. 3341

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation   | Content | From | To | Size   | Put in | Pulled out |
|-------------|---------|------|----|--------|--------|------------|
| Mississippi | Dry     | 224  | 0  | 8-5/8" | 224    | 0          |
|             |         |      |    |        |        |            |
|             |         |      |    |        |        |            |
|             |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.  
Drill to rotary total depth of 3341. Fill with heavy mud to 1100'. Pump in 35 sacks cement. Fill with heavy mud to 275'. Pump in 35 sacks cement. Fill with heavy mud to 60'. Pump in 25 sacks to fill from 60' to surface. Plug rat-hole with 10 sacks cement. Plug water well with 10 sacks cement.  
 (if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Tornado Drilling, Inc. License No. 3890

Address P.O. Box 37, Canton, Kansas 67428

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Ralph R. Hamilton

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]  
 (Address) 310 West Central - Suite 117 Wichita, Kansas 67202



SUBSCRIBED AND SWORN TO before me this 7th day of February, 19 90

[Signature]  
 Notary Public

My Commission Expires: December 6, 1992

TORNADO DRILLING, INC.  
P.O. BOX 37  
CANTON, KANSAS 67428  
February 1, 1990

COMPANY: VESS OIL CORPORATION  
CONTRACTOR: TORNADO DRILLING, INC.  
FARM: M & L LAND COMPANY #1  
LOCATION: 1980' FSL AND 3630' FEL SECTION  
22-26S-2E, SEDGWICK COUNTY, KANSAS  
COMMENCED: JANUARY 16, 1990  
COMPLETED: JANUARY 26, 1990  
ELEVATION:

|      |    |      |                    |                        |
|------|----|------|--------------------|------------------------|
| 0    | to | 40   | Soil and clay      |                        |
| 40   | to | 185  | Sand & Shale       |                        |
| 185  | to | 231  | Lime               |                        |
| 231  | to | 346  | Lime, Shale & Sand |                        |
| 346  | to | 730  | Shale & Lime       |                        |
| 730  | to | 1075 | Lime & Shale       |                        |
| 1075 | to | 1435 | Shale & Lime       |                        |
| 1435 | to | 1670 | Lime & Shale       |                        |
| 1670 | to | 1925 | Shale & Lime       |                        |
| 1925 | to | 2185 | Lime & Shale       |                        |
| 2185 | to | 2328 | Lime & Shale       |                        |
| 2328 | to | 2475 | Lime               |                        |
| 2475 | to | 2623 | Shale & Lime       | KC Top 2483'           |
| 2623 | to | 2750 | Lime               |                        |
| 2750 | to | 2855 | Lime               |                        |
| 2855 | to | 2923 | Lime               | Miss. Top 2910' DST #1 |
| 2923 | to | 2934 | Mississippi        |                        |
| 2934 | to | 3040 | Mississippi        |                        |
| 3040 | to | 3106 | Lime               |                        |
| 3106 | to | 3180 | Lime               |                        |
| 3180 | to | 3208 | Lime               | DST #2 3143'-3208'     |
| 3208 | to | 3275 | Lime               |                        |
| 3275 | to | 3327 | Lime & Sand        | DST #3 3301'-3327'     |
| 3327 | to | 3341 | Lime               | DST #4 3298'-3341'     |
|      |    | 3341 | Rotary Total Depth |                        |

RECEIVED  
STATE OF KANSAS COMMISSION  
FEB 8 1990  
CONSERVATION DIVISION  
Wichita, Kansas

Drill 12 1/4" hole to 231'. Run 226' 8-5/8" surface casing set at 224' with 160 sacks 60/40 Pozmix, 3% c/c, 2% gel. Plug down at 12:00 P.M., January 17, 1990. Drill 7-7/8" hole to rotary total depth of 3341'. Fill with heavy mud to 1100'. Pump in 35 sacks cement. Fill with heavy mud to 275'. Pump in 35 sacks cement. Fill with heavy mud to 60'. Pump in 25 sacks cement to fill to surface. Plug rathole with 10 sacks cement. Plug water well with 10 sacks cement. Job complete @ 9:30 A.M., January 26, 1990. Released rig.

CERTIFICATE

I, Terry P. Bandy, President of Tornado Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy of log on your M & L Land Company # 1 located on the 1980' FSL and 3630' FEL of section 22-26S-2E, Sedgwick County, Kansas as is reflected by the files of Tornado Drilling, Inc.

CYNTHIA G. REIMER  
NOTARY PUBLIC  
STATE OF KANSAS  
MY APPL. EXPIRES 6-14-90

Terry P. Bandy  
Terry P. Bandy, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 1st day of February, 1990.

Cynthia G. Reimer  
Cynthia G. Reimer - Notary Public