

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-173-20, 812

LEASE NAME Lygrisse

WELL NUMBER 22-1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 22 TWP. 26S RGE. 2E (E) or (W)

COUNTY Sedgwick

Date Well Completed         

Plugging Commenced 8-28-89

Plugging Completed 9-6-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR H-30 Inc

ADDRESS 251 N. Water Suite 10, Wichita, Ks

PHONE# (316) 263-2043 OPERATORS LICENSE NO. 5107

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on September 6, 1989 (date)

by Don Thompson (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 3319'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8	250'	0
				5-1/2	3300'	2423'

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1989  
Wichita, Kansas  
CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Strung up long stroke jars & ripper. PLUG BACK WITH GRAVEL TO 3250'. Mix & dump 6 sacks cmt @ 3250'. Rip 5 1/2" csg @ 2520' & 2423'. Rip 5 1/2" @ 2300' & 2200'. Pulled 75 jts 5 1/2" csg- 2423'. Put rock bridge 300' to 280'. Bail hole dry @ 280'. Had 5 yds slurry mix put 280' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor DALE Wilson - W. W. Drilling Co. License No. 06012

Address RR #3 Box 66, El Dorado, Kansas 67042

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: H-30 Inc.

STATE OF Kansas COUNTY OF Butler, ss.

Dale Wilson- plugging contractor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Dale Wilson

(Address) RR #3 Box 66, El Dorado, Ks 67042

SUBSCRIBED AND SWORN TO before me this 20<sup>th</sup> day of September, 19 89

Ernst Estermaehle  
Notary Public

My Commission Expires:

