

TIGHT ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 32309
Name: Presco Western, LLC
Address: 5480 Valmont, Ste. 350
City/State/Zip: Boulder, CO 80301
Purchaser: Plains Marketing LP - oil OneOK - gas
Operator Contact Person: Leonard Witkowski
Phone: (303) 444-8881
Contractor: Name: Cheyenne Drilling LP
License: 33375
Wellsite Geologist: None - Boulder office

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

11/04/2005	11/14/2005	11/21/2005
Spud Date or Recompletion Date	Date Reached TD	Completion Date or Recompletion Date

API No. 15 - 081-21625-00-00
County: Haskell
C NW SE Sec. 24 Twp. 30 S. R. 34 East West
1980 feet from S N (circle one) Line of Section
1980 feet from E W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Gamer Well #: 11-J24-30-34
Field Name: Victory
Producing Formation: Morrow/St. Louis
Elevation: Ground: 2960.3 Kelly Bushing: 2971.3
Total Depth: 5715 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 1709 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit) *ALT INTRM 8-20-08*
Chloride content 2100 ppm Fluid volume 1400 bbls
Dewatering method used Air Evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Regulatory Specialist Date: 04/04/2006
Subscribed and sworn to before me this 5th day of April,
2006.
Notary Public: [Signature]
Date Commission Expires: 4-7-09

JENNIFER THOMAS
Notary Public
State of Colorado

KCC Office Use ONLY
 Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2006

CONSERVATION DIVISION
WICHITA, KS

J1600

Operator Name: Presco Western, LLC Lease Name: Garner Well #: 11-J24-30-34
 Sec. 24 Twp. 30 S. R. 34 East West County: Haskell

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Sonic cement bond, Dual compensated Porosity, Dual induction	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:70%;">Name</td> <td style="width:15%;">Top</td> <td style="width:15%;">Datum</td> </tr> <tr> <td>Heebner</td> <td>4050</td> <td>-1079</td> </tr> <tr> <td>Lansing</td> <td>4120</td> <td>-1149</td> </tr> <tr> <td>Kansas City</td> <td>4590</td> <td>-1619</td> </tr> <tr> <td>Marmaton</td> <td>4752</td> <td>-1781</td> </tr> <tr> <td>Pawnee</td> <td>4860</td> <td>-1889</td> </tr> <tr> <td>Ft Scott</td> <td>4900</td> <td>-1929</td> </tr> <tr> <td>Morrow</td> <td>5242</td> <td>-2271</td> </tr> <tr> <td>St Genevieve</td> <td>5336</td> <td>-2365</td> </tr> </table>	Name	Top	Datum	Heebner	4050	-1079	Lansing	4120	-1149	Kansas City	4590	-1619	Marmaton	4752	-1781	Pawnee	4860	-1889	Ft Scott	4900	-1929	Morrow	5242	-2271	St Genevieve	5336	-2365
Name	Top	Datum																										
Heebner	4050	-1079																										
Lansing	4120	-1149																										
Kansas City	4590	-1619																										
Marmaton	4752	-1781																										
Pawnee	4860	-1889																										
Ft Scott	4900	-1929																										
Morrow	5242	-2271																										
St Genevieve	5336	-2365																										

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24	1709	Comm/Lite	150/575	Comm3%CC;Lite 3%CC1/4Flowseal
Production	7-7/8"	5-1/2"	15.5	5185	ASC	200	10%seal;5#Gtl; .5%FL160;2%gel

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
4	5034-5038	Acidize well 2000g NEFE; 45 bbls 2% flush	
4	5006-5010	Acidize well 2000g NEFE; 45 bbls 2% flush	
4	4900-4925	Acidize well 2000g NEFE; 45 bbls 2% flush	
4	4410-4415	Acidize well 1500g MEFD; 45 bbls 2% flush	

TUBING RECORD	Size 2.875	Set At 4650	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
---------------	----------------------	-----------------------	-----------	---

Date of First, Resumerd Production, SWD or Enhr. 12/28/2005	Producing Method <input checked="" type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)
---	---

Estimated Production Per 24 Hours	Oil Bbls. 4	Gas Mcf 2	Water Bbls. 4	Gas-Oil Ratio 427	Gravity 37.5
-----------------------------------	-----------------------	---------------------	-------------------------	-----------------------------	------------------------

Disposition of Gas: Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION: Open Hole Perf. Dually Comp. Commingled

Production Interval: Other (Specify) _____

ALLIED CEMENTING CO., INC.

71644
21682

Federal Tax I.D.

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

oakley

DATE <u>11-5-05</u>	SEC. <u>24</u>	TWP. <u>30s</u>	RANGE <u>34w</u>	CALLED OUT	ON LOCATION <u>10:00 P.M.</u>	JOB START <u>11:30 AM</u>	JOB FINISH <u>12:30 AM</u>
LEASE <u>Garner</u>	WELL # <u>11-524</u>	LOCATION <u>Satanta 1 1/4 S W 13</u>			COUNTY <u>Haskell</u>	STATE <u>KS</u>	
OLD OR <input checked="" type="checkbox"/> NEW (Circle one)							

CONTRACTOR Cheyeme Prlg Rig 1
 TYPE OF JOB Surface
 HOLE SIZE 12 1/4 T.D. 1715'
 CASING SIZE 8 5/8 DEPTH 1709'
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT 40.33
 CEMENT LEFT IN CSG. 40.33
 PERFS:
 DISPLACEMENT 106 1/4
 EQUIPMENT

OWNER Same
 CEMENT
 AMOUNT ORDERED 150 sks Com 3% CL
57.5 sks Lite 3% CL 1 1/4" Plug Seal
 COMMON 150 sks @ 10.00 1500.00
 POZMIX @
 GEL @
 CHLORIDE 24 sks @ 38.00 912.00
 ASC @
 Lite 57.5 sks @ 9.30 5347.50
 Plug Seal 144 @ 17.00 2448.00
 RECEIVED
 KANSAS CORPORATION COMMISSION
 APR 06 2006
 CONSERVATION DIVISION
 WICHITA, KS
 HANDLING 77.5 sks @ 1.60 1244.80
 MILEAGE 64 / 9k/mile 1400.40
 TOTAL 10649.50

PUMP TRUCK CEMENTER Dean
 # 373-281 HELPER Andre
 BULK TRUCK
 # 377 DRIVER MALT
 BULK TRUCK
 # 218 DRIVER Larry
386 Lonnie

REMARKS:
Mix 57.5 sks Lite 3% CL 1 1/4" Plug Seal
150 sks Com 3% CL, Disp 106 1/4 866
Water Cement d/d 6% water
Plug handled
Plug Head

Thank you

SERVICE
 DEPTH OF JOB
 PUMP TRUCK CHARGE 1320.00
 EXTRA FOOTAGE @
 MILEAGE 30 mile @ 5.00 150.00
 MANIFOLD @
 TOTAL 1470.00

CHARGE TO: Presco Western
 STREET
 CITY STATE ZIP

8 5/8" PLUG & FLOAT EQUIPMENT
 Guide Shoe @ 235.00
 AKU Insert @ 325.00
 4 Centralizers @ 55.00 220.00
 1 Bas Key @ 180.00
 1 8 5/8 Rubber Plug @ 100.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment

ALLIEL CEMENTING CO., INC.

21692

T16-117

Federal Tax I.D.

EMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Ogkley

DATE <u>11-14-05</u>	SEC <u>24</u>	TWP. <u>30s</u>	RANGE <u>39W</u>	CALLED OUT	ON LOCATION <u>8:00 AM</u>	JOB START <u>5:15 PM</u>	JOB FINISH <u>6:00 PM</u>
LEASE <u>Garner</u>	WELL # <u>11-524</u>	LOCATION <u>Satanta 1/4 S W1S</u>	COUNTY <u>Haskell</u>	STATE <u>KS</u>			
OLD OR <input checked="" type="radio"/> NEW (Circle one)							

CONTRACTOR Cheyenne Drilling Rig 1
 TYPE OF JOB 5 1/2 Production string
 HOLE SIZE 7 1/8 T.D. 5715'
 CASING SIZE 5 1/2 DEPTH 5185.27
 TUBING SIZE DEPTH
 DRILL PIPE DEPTH
 TOOL Port Collar DEPTH
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT 21.15'
 CEMENT LEFT IN CSG. 21.15'
 PERFS.
 DISPLACEMENT 123 Bbls
 EQUIPMENT

OWNER Same
 CEMENT
 AMOUNT ORDERED 200 SKS ASC, 290 gals
WPR 2 500 gals, 58 gals Gelsolite, 50 gals
PL 160 500 gals WPR-2
 COMMON @
 POZMIX @
 GEL 4 SKS @ 14.00 56.00
 CHLORIDE @
 ASC 200 SKS @ 11.65 2330.00
Gelsolite 1000g @ .60 600.00
Salt 26 SKS @ 15.75 409.50
PL 160 94g @ 8.70 817.80
 @
WPR-2 500gals @ 1.00 500.00
 @
 @
 @
 HANDLING 263 SKS @ 1.60 420.80
 MILEAGE 64/34 mile 473.40
 TOTAL 6607.50

PUMP TRUCK CEMENTER Dean
 # 373-281 HELPER Andrew/Max
 BULK TRUCK
 # 218 DRIVER Lennie
 BULK TRUCK
 # DRIVER

REMARKS:

pump 500gals w/PR-2 down CSG.
Plug Rat Hole w/15SKS,
Plug mouse Hole w/10SKS,
Pump 17.5SKS cement down 5 1/2 CSG.
Had lift pressure 1200#,
Plug landed at 1600#,
Float held.

Thank you

CHARGE TO: Presco western
 STREET _____
 CITY _____ STATE RECEIVED

KANSAS CORPORATION COMMISSION

APR 06 2006

To Allied Cementing Co., CONSERVATION DIVISION
 You are hereby requested to rent WICHITA, KS equipment
 and furnish cementer and helper to assist owner or
 contractor to do work as is listed. The above work was
 done to satisfaction and supervision of owner agent or
 contractor. I have read & understand the "TERMS AND
 CONDITIONS" listed on the reverse side.

SERVICE

DEPTH OF JOB
 PUMP TRUCK CHARGE 1510.00
 EXTRA FOOTAGE @
 MILEAGE 30 miles @ 5.00 150.00
 MANIFOLD @
Head Rental @ 75.00
 @
 TOTAL 1735.00

PLUG & FLOAT EQUIPMENT

Triplex shoe 1300.00
Latch down Plug Assy @ 350.00
1 - centralizers @ 50.00 350.00
1 - Basket @ 140.00
1 - Port Collar @ 1750.00
 @
 TOTAL 3890.00

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Rodney Gonzales

Rodney Gonzales
 PRINTED NAME

ALLIED CEMENTING CO., INC.

21675

T164T

Federal Tax I.C. [REDACTED]

MIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

DARLEY

DATE <u>11-18-05</u>	SEC. <u>24</u>	TWP. <u>30S</u>	RANGE <u>34W</u>	CALLED OUT	ON LOCATION <u>2:00 PM</u>	JOB START <u>3:00 PM</u>	JOB FINISH <u>4:45 PM</u>
LEASE <u>GARNER</u>	WELL # <u>11-J</u>	LOCATION <u>SATANTA 1S-W IN</u>	COUNTY <u>HASKELL</u>	STATE <u>KS</u>			

OLD OR (NEW) (Circle one)

CONTRACTOR Eldridge Well Service OWNER SAME

TYPE OF JOB PORT COLLAR

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2" DEPTH _____

TUBING SIZE 2 1/2" DEPTH 3015'

DRILL PIPE _____ DEPTH _____

TOOL PORT COLLAR DEPTH 3015'

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT 16 3/4 BBL

EQUIPMENT

PUMP TRUCK CEMENTER FERRY

191 HELPER JARROLD MAX

BULK TRUCK _____

394 DRIVER A/AN

BULK TRUCK _____

_____ DRIVER _____

REMARKS:

PRESSURE SYSTEM TO 1500 PSI.
OPEN PORT COLLAR MIX 450 SKS
LETE 1/4" FLO-SEAL + DISPLACE 16 3/4 BBL
CLOSE PORT COLLAR PRESSURE TO 1500 PSI
RUN 2 JTS REVERSE OUT.

THANK YOU

CHARGE TO: PRESCO - WESTERN

STREET _____

CITY _____ STATE _____

CEMENT AMOUNT ORDERED
450 SKS LETE 1/4" FLO-SEAL

COMMON @ _____
POZMIX @ _____
GEL @ _____
CHLORIDE @ _____
ASC @ _____

LETE 450 SKS @ 8.80 3960.00

FLO-SEAL 113# @ 1.70 192.10

HANDLING 481 SKS @ 1.60 769.60

MILEAGE 64 PER SK / MILE 865.80

TOTAL 5787.80

SERVICE

DEPTH OF JOB 3015'

PUMP TRUCK CHARGE 785.00

EXTRA FOOTAGE @ _____

MILEAGE 30 MI @ 5.00 150.00

MANIFOLD @ _____

TOTAL 935.00

RECEIVED
KANSAS CORPORATION COMMISSION

APR 06 2006

CONSERVATION DIVISION
WICHITA, KS

PLUG & FLOAT EQUIPMENT

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE [Signature]

[Signature]
PRINTED NAME

TOTAL _____