

*file
mem
7/7/08*

WELL PLUGGING APPLICATION
PLEASE TYPE FORM and File ONE Copy

API #: 15-079-20405-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued,

Indicate spud or completion date: 4/16/1979

Well Operator: American Energies Corporation KCC LICENSE # 5399
(owner/company name) (operator's)

Address: 155 North Market CITY: Wichita

State: Kansas Zip Code: 67202 Contact Phone: 316-263-5785

Lease: R/Graber R (Well #: 1) Sec. 15 Twp. 22S R. 2W

NE - SW - SW Spot Location/QQQQ County: Harvey

940' Feet (in exact footage) From North South (from nearest outside section corner) Line of Section (Not Lease Line)

1220' Feet (in exact footage) From East West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8" Set at: 212' Cemented with: 150 sx Sacks

Production Casing Size: 4 1/2" Set at: 3206' Cemented with: 75 sx Sacks

List (ALL) Perforations and Bridgeplug Sets: _____

Perforated Mississippi from 3173-3176, 3180-3184

Elevation: 1446 (G.L./K.B.) T.D. 3207 PBTD: _____ Anhydrite Depth: _____

Condition of Well: Good _____ Poor _____ Casing Leak _____ Junk in Hole _____
(Stone Corral Formation)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Place 50' sand plug over perms. Fill hole with mud and set a 35 sx plug @ 450' and fill to surface with cement.

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 03 2008

CONSERVATION DIVISION
WICHITA, KS

Is Well Log attached to this application as required? No (Yes/No) Is ACO-1 Filed? Yes (Yes/No)

If Not explain why? Currently on file with state

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. Seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Doug Ward

Phone: 620-654-7149

Address: P.O. Box 516, 136 N. Main City: Canton State: Kansas

Plugging Contractor: American Energies Corporation KCC LICENSE #: 5399
(company name) (contractor's)

Address: P.O. Box 516, 136 N. Main City: Canton State: Kansas Zip 67428

Proposed Date and Hour of Plugging (if known?): As soon as possible

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 06/30/08 Authorized Operator/Agent: Alan L. DeGood
(signature) Alan L. DeGood, President

S & S OIL CO. #1 R. GRABER 15-22-2W
 R.R. #2 BURRETON, KS 67020 940' FSL &
 CONTR BLACKSTONE DRLG., INC. CTY HARVEY 1220' FWL, SW/4

GEOL _____ FIELD ALTA MILLS EXT (1/4 N E)

E 1446 KB CM 4/16/79 CARD ISSUED 10/20/79 IP F 2000 MCFGPD
 MISS 3173-84 OA

+	+
+	+

API 15-079-20,405

SMP	TOPS	DEPTH	DATUM
HEEB		2174	- 728
TOR		2194	- 748
DOUG SH		2205	- 759
DOUG SD		2306	- 860
BR LM		2360	- 914
LANS		2424	- 978
BKC		2828	-1382
CHER		3036	-1590
MISS WAR		3129	-1683
RTD		3207	-1761

N/A No Geolog 136479 MCT
 8-5/8" 212/150sx, 4 1/2" 3206/75sx
 DST (1) 3133-69 (MISS)/30-30-30-30, 90'
 O&VSGCM, SIP 800-731#, FP 79-79/
 79-79#, BHT 106°
 DST (2) 3170-93 (MISS)/30-30-60-30, GTS
 7", GA 60 MCFG/20" (2ND OP) GA 106
 MCFG, REC 30' O&GCM, SIP 1095-1075#
 FP 50-60/40-89#
 MICT - CO, PF (MISS) 3173-76, 3180-84,
 TSTD, GSG, SI OF 2000 MCFGPD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

RECEIVED
 KANSAS CORPORATION COMMISSION

JUL 03 2008

CONSERVATION DIVISION
 WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

AMERICAN ENERGIES CORPORATION
155 N MARKET STE 710
WICHITA, KS 67202-1821

July 07, 2008

Re: GRABER R #1
API 15-079-20405-00-00
15-22S-2W, 990 FSL 1220 FWL
HARVEY COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after January 3, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000