

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

*KCC  
ML  
7/7/08*

API # 15 - 055-10,168 - 6000 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 11-9-61

Well Operator: Hartman Oil Co., Inc. KCC License #: 30535

Address: 12950 E. 13th St. N. City: Wichita

State: Kansas Zip Code: 67230-1457 Contact Phone: (620) 277 - 2511

Lease: [Graves Vance (Pinex)] Well #: (1) Sec. 9 Twp. 22 S. R. 33  East  West

SW - SW - SW Spot Location / QQQQ County: Finney

320 319 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

320 4926 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

*Hgs  
Pa  
SRS  
6/20/08*

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: n/a Set at: n/a Cemented with: n/a Sacks

Surface Casing Size: 8-5/8" Set at: 418' Cemented with: 100 com + 150 Pozmix Sacks

Production Casing Size: 5-1/2" Set at: 4821' Cemented with: 175 Poz + 50 Trinity Sacks

List (ALL) Perforations and Bridgeplug Sets: Perfs - 4406-12' Marmanton, - 4433-40' Ft.Scott, - 4710-28' St. Gene, - 4650-75' Morrow  
4753-64' St. Louis

Elevation: 2901.5 ( G.L. /  K.B.) T.D.: 4822' PBTD: 4788' Anhydrite Depth: \_\_\_\_\_ (Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Set 1st CIBP @ 4350' w/ 2 sks cement - Set 2nd CIBP @ 1150' w/ 2 sks

Perforate 2 holes @ 1100' - Pump (260 sks) or csg volume plus 80 sks - 60-40 poz w/ 4% gel down 5-1/2" Csg - Pump (200 sks) 60-40 poz w/ 4% gel  
down 8-5/8" x 5-1/2" Csg annulus

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? Drilled - 11-9-61

**Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.**

List Name of Company Representative authorized to be in charge of plugging operations: Stan Mitchell

Hartman Oil Co., Inc. Phone: (620) 277 - 2511

Address: 4550 9 Mi Rd - Garden City City / State: Ks. 67846

Plugging Contractor: Allied Cement Co. KCC License #: 30535 99996

Address: P O Box 27 - Oakley, Ks. Phone: (785) 672 - 3452

Proposed Date and Hour of Plugging (if known?): 6/20/08 @ 9:00 AM

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 6/19/08 Authorized Operator / Agent: St. Mitchell (Signature)

RECEIVED  
KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202 **JUL 03 2008**

*\* Well Abn. Plugged - KCC - ML -*

*Dist. 1*  
CONSERVATION DIVISION  
WICHITA, KS