

2030826

6-29

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20,593-00-00

N/2 SE SE, SEC. 13, T 26 S, R 2 W/E

990 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5446

Lease Name Wheeler Well # 2

Operator: Benjamin Giles

County Sedgwick 108.88

Name & Address 321 E. William

Well Total Depth 3350 feet

Wichita, KS 67202

XXXXXXXX Pipe: Size 5-1/2" feet 3348'/100 sx

Surface Casing: Size 8-5/8" feet 250' C.T.S.

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 108, Geneseo, KS 6698

Company to plug at: Hour: Day: 22 Month: 6 Year: 19 88

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-824-6467

were: Fill with sand to 3150' - dump 5 sx cement - shoot & pull casing -
set top bridge 300' - fill to surface with cement.

Perf 3197' to 98'

Plugging Proposal Received by Dist #2
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 19:30 Day: 29 Month: 6 Year: 19 89

ACTUAL PLUGGING REPORT Filled hole with sand 3140' - dumped 5 sx cement with

bailer - shot & pulled 2202' of 5-1/2" casing - could not bail hole -

Consolidated Inc. #80759 pumped 6 sx gel, 2 sx hulls, 1000 sx 50-50 posmix 4%

gel down 8-5/8" csg. Pump press 400# SI press 50#

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
7-24-89

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

(Do not XXXXXX observe this plugging.)

DATE 7-25-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25410