

2-26

2-030999

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-173-20,819-00-00

C N/2 NW SW, SECTION 13 TOWNSHIP 26 RANGE 2E

OPERATOR LICENSE # 5446

2310 FEET FROM S SECTION LINE

4620 FEET FROM E SECTION LINE

OPERATOR Benjamin M. Giles

NAME & 321 E. William, #207

ADDRESS Wichita, KS 67202

LEASE NAME: Kraft Properties #1

COUNTY: Sedgwick 108.71

WELL TOTAL DEPTH: 3345' PB 3016'

PIPE: 4-1/2" @ 3016'/50 sx

SURFACE CASING: 8-5/8" @ 250' C.T.S.

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: McPherson Drilling

ADDRESS: Augusta, KS 67010 LICENSE: 5495

COMPANY TO PLUG AT: HOUR: \_\_\_\_\_ DAY: 13 MONTH: 2 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Billy McPherson

COMPANY NAME: McPherson Drilling Company PHONE: (5495)

WERE: Sand 50' above perms 5 sx cmt - shoot & pull 4-1/2"  
csg - set rock bridge 250' - cmt to surf.

Perfs 2889' to 2891'

PLUGGING PROPOSAL RECEIVED BY: Dist #2 office

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: \_\_\_\_\_ DAY: 26 MONTH: 2 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded hole to 2830' - dumped 4 sx cmt w/bailer -  
shot & pulled 2390' of 4-1/2" csg - ran 2-3/8" tub to  
330' - Knebler Concrete #031419 dumped 5-1/2 yds  
slurry mix to surf - pulled tub - cmt fell down hole -  
on 2/28/91 Knebler Concrete #31495 dumped 1-1/2  
yds slurry mix to surface.

REMARKS: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE 3-22-91

INV. NO. 31232

Don Thompson  
Don Thompson (AGENT)

MAR 12 1991  
3-12-91  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
REV. 3/90

2-26 JUN 06 1991

DW