

2 030553

10-27-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 173-20.601-~~00~~-01

SE NW NW, SEC. 17, T 26 S, R 2 XW/E

4290 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5037

Lease Name Galyardt Well # 11-A

Operator: Pan-Western Petroleum, Inc.

County Sedgwick 80.96

Name & Address Board of Trade Center, #501

Well Total Depth 2491 feet

120 S. Market

Conductor Pipe: Size 4 1/2" feet 3489

Wichita, KS 67202

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Jonathan Oil License Number 4231

Address El Dorado, KS 67042

Company to plug at: Hour: 08:30 Day: 26 Month: 10 Year: 1987

Plugging proposal received from Len Butler

(company name) Jonathan Oil (phone)

were: Perf @3464-3469. Sand 50' above perf and dump 6 sxs cement. Shoot and pull 4 1/2" casing. Pump 3 sxs hulls, 12 wxs gel, 100 sxs cement down 8 5/8" surface casing.

Plugging Proposal Received by District #2 Office-J. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 15:20 Day: 27 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 70' gravel dumped 5 sxs cement w/bailer. Shot and pulled 2763' of 4 1/2" casing. United #0961 pumped 2 sxs hulls, 12 sxs gel, 100 sxs 60/40 pozmix down 8 5/8" casing. P.P. 800# SIP 350#

Remarks: Top plug (If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

NOV 2 1987

11-2-87

CONSERVATION DIVISION
Wichita, Kansas

Signed

Alon Thompson (TECHNICIAN)

DATE 11-10-87

INV. NO. 18820

Handwritten initials