

2 100153

API NUMBER 15-173-20312-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3004

Operator: Gressel Oilfield Service  
Name & Address: Box 607  
Burrton, KS 67020

\_\_\_\_\_ feet from S section line  
\_\_\_\_\_ feet from E section line

Lease Name Galyardt Well # 6

County Sedgwick 114.11

Well Total Depth 3511 PBSD 3434 feet

~~Construction~~ Pipe: Size 4 1/2 feet 3474-150sks

Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated perf 3460-62 1/2

Plugging Contractor Gressel Oilfield Service License Number 3004

Address Box 607

Company to plug at: Hour: 2:30 Day: 8 Month: 8 Year: 1986

Plugging proposal received from Ed Gressel

(company name) Gressel Oilfield Service (phone) \_\_\_\_\_

were: dump sand to 50' above perfs. with 4 sacks of cement on bottom - pull  
recoverable pipe - bail fluid to 50' below surface - build bridge dump redi-mix to  
surface

Plugging Proposal Received by District 2  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 Day: 8 Month: 8 Year: 1986

ACTUAL PLUGGING REPORT Sanded to 3350 feet and dumped 4 sacks of cement. Pulled 1890  
feet of 4 1/2" (63 joints). Set bridge at 325 feet (25'). Dumped bailed fluid  
to 300 feet: Dumped redi-mix from 300 feet to surface.

Remarks: Rudd & Son Redi-mix #88984 3 1/2 yards  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 15 1986

INV. NO. 14732

8-8

SEP 10 1986

AUG 14 1986

8-14-86

Signed J. L. Sanders  
(TECHNICIAN)